

KIRORI MAL COLLEGE
UNIVERSITY OF DELHI
DELHI-110007

Sealed quotations are invited from the contractors of appropriate class registered with CPWD, M.E.S, Railways or working contractors of University of Delhi for the work "Repair of floor and painting work in Principal's office at Kirori Mal College , University of Delhi" so as to reach the college office by 4.00 p.m. on 14.02.2024.


S. No	Description of Items	Unit	Qty	Rate	Amount
1	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge.	cum	2	411.3	822.60
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 4.1.2 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	0.5	7783.65	3891.83
3	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, proved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. Glazed vitrified floor tiles polished finish				
	Size of Tile 600 x 600 mm	sqm	10	1359.2	13592.00
	Size of Tile 600 x 1200 mm	sqm	65	1612.75	104828.75
4	Deduct for not using 20 mm thick cement mortar 1:4 (1 cement : 4coarse sand) bedding in laying of floor tiles and jointing with grey cement slurry @ 3.3 kg/sqm.	sqm	65	-735.3	-47794.50
5	Fixing glazed/ Ceramic/ Vitrified floor tiles with cement based high polymer modified quick-set tile adhesive (Water based) conforming to IS: 15477, in average 3mm thickness.	sqm	65	633.6	41184.00
6	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	sqm	15	121.55	1823.25
7	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats on new work	sqm	225	137.85	31016.25
8	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sqm	225	123.85	27866.25
9	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	220	20.85	4587.00
10	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)	sqm	5	462.3	2311.50
11	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	cum	0.5	2007.1	1003.55
				Total	185132.48

Conditions:

1. The work is to be completed in 45 days.
2. 1% water/electricity charges will be recovered.
3. CPWD Specifications will be followed rigidly.
4. Rates should be quoted both in words & figures.
5. Undersigned reserves the authority to reject any or all the quotations without assigning any reason thereof.

I/we hereby quote my/ our rates @ _____% above/ below the above estimated rates.

Contractor


 Principal
 (प्रो. दिव्यंशु खट्टर)
 Prof. Divyanshu Khattar
 प्राचार्य (Principal)

किरोड़ी मल कॉलेज/Kirori Mal College
 दिल्ली विश्वविद्यालय/University of Delhi
 दिल्ली-110007/Delhi-110007